



WORK PROPOSAL

Proposal No.: JRG-2026-004

Date: August 10, 2026

Valid for: 30 days

Structural & Ornamental Welding · Aluminum · Steel · Stainless · Exterior Renovation

13796 SW 139 Ct, Miami, FL 33186 · (786) 804-9010 · [Email] · Lic. [License #]

PREPARED FOR

Client: Raul [Last Name]
Project Address: 18398 131st Trail N, Jupiter Farms, FL
Phone / Email: [Client Contact]

PROJECT

Elevated deck hardware renewal — four (4) deck structures: two (2) at the barn and two (2) at the pool house. All new connectors and fasteners, railing-fascia reinforcement, eight (8) joists and the long column tie rods replaced.

1. EXISTING CONDITIONS

Four (4) elevated deck structures at the property — the two (2) identical decks at the barn and the two (2) decks at the pool house — show **advanced corrosion in the structural hardware**: galvanized joist hangers, framing angles and post brackets are rusted, and the long galvanized all-thread rods that tie the framing to the main columns are oxidized. The fascia boards where the railings are mounted have worked loose. In addition, eight (8) deck joists show deterioration and require replacement. The remaining framing lumber is sound.

2. SCOPE OF WORK (ALL FOUR DECKS)

- 1. **Connectors — ALL NEW, with ALL NEW NAILS**: Remove and replace every joist hanger, framing angle/clip and post bracket on all four (4) deck structures with new **heavy-galvanized ZMAX / G185 (triple-zinc) connectors** rated for exterior use and treated lumber. **Every connector is installed with all-new hot-dip galvanized structural nails — no old nails or fasteners are re-used anywhere.** Estimated count: approximately 230 connectors on the barn decks plus the pool-house decks — final total count field-verified.
- 2. **Railing-fascia reinforcement**: The fascia boards where the railings are mounted are loose. Each railing-mount fascia will be **reinforced and re-secured with additional structural screws** through to the framing, and all railing connections tightened — railings left firm, no movement.
- 3. **Long column tie rods — replace ALL**: Remove the long rusted galvanized all-thread rods that tie the joists/framing against the main support columns, and replace with **new hot-dip galvanized all-thread rods** with new galvanized nuts and washers, re-tensioned.
- 4. **Joist replacement**: Remove and replace eight (8) deteriorated deck joists with new pressure-treated lumber matched to the existing size and length; deck boards carefully lifted and re-fastened; new hangers with new nails at each replaced joist included in the connector count.
- 5. **Sequence & safety**: Connectors replaced one at a time — the structure remains fully supported at all times.
- 6. **Closeout**: Final inspection of every connection, cleanup, and walkthrough with owner.

3. PRICE

Item	Amount
------	--------

Complete hardware renewal — four (4) deck structures (barn ×2 + pool house ×2): all connectors replaced with ZMAX/G185 triple-zinc and all-new galvanized nails, railing-fascia reinforcement with additional structural screws, all long galvanized column tie rods replaced new, and eight (8) deck joists replaced in pressure-treated lumber — materials & labor	\$ 15,000.00
TOTAL — ALL FOUR DECKS, MATERIALS & LABOR	\$ 15,000.00

4. TERMS & CONDITIONS

- **Payment:** [50%] deposit to schedule and order material; balance due upon completion and owner walkthrough.
- **Schedule:** Approx. one (1) to two (2) weeks, weather permitting.
- **Warranty:** One (1) year on workmanship; connectors and hardware per manufacturer specification for exterior/treated-lumber service.
- **Exclusions:** Railing replacement (railings are reinforced and tightened as described, not replaced), deck boards other than those lifted for joist replacement, stairs, posts and beams (sound, remain), painting/sealing of wood, and repair of any additional rot found (quoted by written change order).
- Any additional work will be quoted and approved in writing before proceeding (change order).

JRG Welding Corp — Authorized Signature / Date

Client Acceptance — Signature / Date