



BUDGETARY ESTIMATE

Ref.: JRG-EST-2026-001

Date: August 27, 2026

Structural & Ornamental Welding · Aluminum · Steel · Stainless · Exterior Renovation

For budgeting only — not a contract

13796 SW 139 Ct, Miami, FL 33186 · (786) 804-9010 · [Email] · Lic. [License #]

PREPARED FOR

Client: Raul [Last Name]
Project Address: 18398 131st Trail N, Jupiter Farms, FL
Phone / Email: [Client Contact]

CONCEPT UNDER CONSIDERATION

Replace all wood deck flooring on both elevated porches (approx. 26' × 50' each — ±2,600 sq ft total) with capped synthetic (composite/PVC-capped) deck boards.

1. WHAT THIS COVERS

Budget-level pricing to remove the existing wood deck boards on both elevated porches and install new **capped synthetic deck boards** — a polymer-protected surface that does not rot, splinter or feed termites, with a 25+ year manufacturer warranty and essentially zero maintenance. Three quality levels are shown so the owner can match the project to his budget. All figures include demolition, disposal, materials, hidden-fastener installation and labor.

2. BUDGET OPTIONS — BOTH PORCHES (±2,600 SQ FT)

Option	What it is	Budget price
A — Veranda® capped composite (by Fiberon) BEST VALUE	The most economical name-brand capped composite. 25-year warranty, wood-look finish in gray or brown. Durable and clean-looking at the lowest cost.	\$ 20,000
B — Trex® Enhance	The best-known composite brand; richer color and slightly tougher cap. 25-year warranty.	\$ 26,000
C — Marine-grade HDPE (WearDeck®)	Dock-grade board made in Florida — the heaviest-duty option, cooler underfoot, lifetime-class durability.	\$ 34,000

3. NOTES

- Prices are **budgetary estimates** based on approximate deck dimensions (26' × 50' each); a firm proposal follows field measurement.
- Synthetic decking requires joists at 16" on-center maximum. Joist spacing will be verified; if additional blocking or intermediate joists are needed, that adjustment is quoted before any commitment.
- Combines naturally with the structural hardware renewal already in progress — the new boards would be installed over the renewed framing.
- Railings, stairs and caps are covered separately (Proposal JRG-2026-005 and the aluminum railing options previously presented).

