



WORK PROPOSAL

Proposal No.: JRG-2026-005

Date: August 26, 2026

Valid for: 30 days

Structural & Ornamental Welding · Aluminum · Steel · Stainless · Exterior Renovation

13796 SW 139 Ct, Miami, FL 33186 · (786) 804-9010 · [Email] · Lic. [License #]

PREPARED FOR

Client: Raul [Last Name]
Project Address: 18398 131st Trail N, Jupiter Farms, FL
Phone / Email: [Client Contact]

PROJECT

Complete rebuild of both deck stairs (two stairs, five steps each) and replacement of the split, weathered railing cap boards on both elevated decks (~200 LF) and stairs.

1. EXISTING CONDITIONS

The two (2) wood deck stairs — five (5) steps each — have treads at the end of their service life: deeply checked, cracked and weathered. The railing cap boards on both elevated decks are split and weathered, with open joints and exposed rusted nails (a safety hazard at the handrail). Approximately 200 linear feet of cap total.

2. SCOPE OF WORK

- 1. **Stairs — complete rebuild (both):** Demolish both existing stairs; furnish and install four (4) new pre-cut pressure-treated ground-contact stringers (two per stair), ten (10) new pressure-treated treads, and galvanized stringer connectors; fastened with exterior-grade structural screws.
- 2. **Stair railing caps:** New pressure-treated 2×6 cap boards on both stair railings.
- 3. **Deck railing caps (~200 LF):** Remove the split and weathered cap boards on both elevated deck railings; install new select pressure-treated 2×6 caps, **screwed (not nailed)**, with joints cut at 45° over posts and sealed — no open joints, no exposed nails.
- 4. **Disposal:** Haul away and legally dispose of all demolished material.
- 5. **Closeout:** Walk every stair tread and every foot of cap, verify solid, cleanup.

3. PRICE

Item	Amount
Both deck stairs — complete rebuild (4 new stringers, 10 new treads, connectors, demolition & disposal)	\$ 1,700.00
Stair railing caps — both stairs	\$ 200.00
Deck railing caps — approx. 200 LF (both elevated decks): removal, new select PT 2×6, screws, sealed 45° joints	\$ 1,800.00
TOTAL — MATERIALS & LABOR	\$ 3,700.00

Cap footage is estimated at ~200 LF and will be field-verified; the unit rate (\$9.00/LF) is honored for any variance. This work is independent of the aluminum railing conversion under consideration — if the owner proceeds with aluminum railings, the deck cap line item is credited/removed.

4. TERMS & CONDITIONS

- **Payment:** Due upon completion.
- **Schedule:** Approx. 2–3 working days, scheduled together with other work at the property.
- **Warranty:** One (1) year on workmanship.
- **Exclusions:** Railing posts and balusters (remain), deck boards, painting/sealing, and repair of concealed rot found at demolition (quoted by written change order).

JRG Welding Corp — Authorized Signature / Date

Client Acceptance — Signature / Date

JRG Welding Corp · Proposal JRG-2026-005 · Thank you for the opportunity to earn your business.