



WORK PROPOSAL

Proposal No.: JRG-2026-002

Structural & Ornamental Welding · Aluminum · Steel · Stainless · Exterior Renovation

Date: **August 26, 2026**

13796 SW 139 Ct, Miami, FL 33186 · (786) 804-9010 · [\[Email\]](#) · Lic. [\[License #\]](#)

Valid for: **30 days**

PREPARED FOR

Client: **Raul** [\[Last Name\]](#)

Project Address: **18398 131st Trail N, Jupiter Farms, FL**

Phone / Email: [\[Client Contact\]](#)

PROJECT

Exterior re-cladding of two (2) storage sheds with James Hardie fiber-cement panel siding, plus new exterior doors (one double, one single) — rot-proof, termite-proof.

1. EXISTING CONDITIONS

Two (2) storage sheds on the property have exterior wood panel cladding with advanced rot deterioration, concentrated at the bottom of the panels where they meet the ground. The walls are 8'-0" high. **Shed 1 (12' × 12')**: three walls are re-clad — the rear wall is protected by its covered porch and remains; its front double door is replaced. **Shed 2 (10'-2" × 10'-2")**: all four walls are re-clad and its single entry door is replaced.

2. PROPOSED SOLUTION — FIBER-CEMENT PANEL SIDING

Re-clad the shed walls with **James Hardie HardiePanel HZ10 vertical siding, Sierra 8 wood-grain texture, 4'×8' sheets, 5/16" thick fiber-cement** — the HZ10 formulation is engineered specifically for hot, humid climates like South Florida:

- **Rot-proof and termite-proof** — cement-fiber composition; nothing to decay, nothing for insects to eat.
- **Weather resistant** — engineered for Florida sun, rain and wind; fire resistant.
- **Wood-grain Sierra 8 texture** with vertical grooves — the finished look of wood siding without its problems.
- Factory-primed finish, ready for paint. **Painting is NOT included in this proposal** — final paint color and painting by owner.

3. SCOPE OF WORK (EACH SHED)

1. **Demolition:** Remove **only the rotted exterior wall boards** — the existing 2×4 stud wall framing is in good condition and **remains in place** as the structure the new panels fasten to. Haul away and legally dispose of debris.
2. **Framing inspection:** With the walls open, inspect the studs and plates. Sound framing is re-used; any rot or termite damage found in the framing is reported to the owner and repaired only under an approved written change order before closing the walls.
3. **Moisture barrier:** Install weather-resistive wrap over the framing on all re-clad walls.
4. **Panel installation:** Install HardiePanel HZ10 Sierra 8 5/16" fiber-cement panels (James Hardie), fastened to the existing 2×4 studs with corrosion-resistant fasteners per James Hardie installation requirements, maintaining the required clearance from grade and concrete (the reason the current panels rotted — the new siding will NOT touch the ground); flashing at tops and corners; joints sealed with exterior sealant; trim at corners and openings.
5. **Exterior doors:** Furnish and install new exterior doors rated for outdoor humidity and heat (fiberglass or steel, Masonite / JELD-WEN or equal — no rust, no rot, no warping): **Shed 1 — one (1) double door 72"×80"** (both

6. **Prime & seal:** All panel cut edges and joints sealed; siding, trim and doors left in factory-primed finish, ready for the owner's painter. **Painting is not included.**

7. **Closeout:** Final cleanup and walkthrough with owner.

- **Payment:** [50%] deposit to schedule and order material; balance due upon completion and owner walkthrough.
- **Schedule:** Approx. [5–7] working days for both sheds, weather permitting; may be scheduled together with the ongoing structural contract to share mobilization.
- **Warranty:** One (1) year on workmanship; siding material per James Hardie manufacturer warranty.

- **Exclusions: Painting (all siding, trim and doors are delivered factory-primed; final paint by owner);** structural framing repair (quoted by written change order if rot/termite damage is found at demolition); roofing; windows; electrical; interior finishes.
- Any additional work will be quoted and approved in writing before proceeding (change order).

JRG Welding Corp — Authorized Signature / Date

Client Acceptance — Signature / Date

JRG Welding Corp · Proposal JRG-2026-002 · Thank you for the opportunity to earn your business.