



WORK PROPOSAL

Proposal No.: JRG-2026-004

Date: August 10, 2026

Valid for: 30 days

Structural & Ornamental Welding · Aluminum · Steel · Stainless · Exterior Renovation

13796 SW 139 Ct, Miami, FL 33186 · (786) 804-9010 · [Email] · Lic. [License #]

PREPARED FOR

Client: Raul [Last Name]
Project Address: 18398 131st Trail N, Jupiter Farms, FL
Phone / Email: [Client Contact]

PROJECT

Elevated deck hardware renewal — two (2) identical porch structures: replace all rusted connectors and threaded rods, and replace eight (8) deteriorated deck joists.

1. EXISTING CONDITIONS

The two (2) identical elevated porch/deck structures at the residence show **advanced corrosion in the structural hardware**: galvanized joist hangers, framing angles and post brackets are rusted, and the galvanized all-thread tie rods ("continuous-thread rods") are oxidized. In addition, eight (8) deck joists show deterioration and require replacement. The remaining framing lumber is sound.

2. SCOPE OF WORK (BOTH STRUCTURES)

- 1. **Connectors — replace ALL:** Remove and replace every joist hanger, framing angle/clip and post bracket on both deck structures with new **heavy-galvanized ZMAX / G185 (triple-zinc) connectors** rated for exterior use and treated lumber, installed with hot-dip galvanized structural fasteners. Estimated count: approximately 230 connectors total (final count field-verified).
- 2. **Threaded rods — replace ALL:** Remove the rusted galvanized all-thread rods and replace with **new hot-dip galvanized all-thread rods**, with new galvanized nuts and washers, re-tensioned. Estimated count: approximately 20 rods (field-verified).
- 3. **Joist replacement:** Remove and replace eight (8) deteriorated deck joists with new pressure-treated lumber matched to the existing size and length; deck boards carefully lifted and re-fastened; new hangers at each replaced joist included in the connector count.
- 4. **Sequence & safety:** Connectors replaced one at a time — the structure remains fully supported at all times.
- 5. **Closeout:** Final inspection of every connection, cleanup, and walkthrough with owner.

3. PRICE

Item	Amount
Complete hardware renewal — both deck structures: all connectors replaced with ZMAX/G185 triple-zinc (~230), all galvanized all-thread rods replaced new (~20), and eight (8) deck joists replaced in pressure-treated lumber — materials & labor	\$ 9,000.00
TOTAL — MATERIALS & LABOR	\$ 9,000.00

4. TERMS & CONDITIONS

- **Payment:** [50%] deposit to schedule and order material; balance due upon completion and owner walkthrough.
- **Schedule:** Approx. 4–6 working days for both structures, weather permitting.
- **Warranty:** One (1) year on workmanship; connectors and hardware per manufacturer specification for exterior/treated-lumber service.
- **Exclusions:** Deck boards other than those lifted for joist replacement, railings, stairs, posts and beams (sound, remain), painting/sealing of wood, and repair of any additional rot found (quoted by written change order).
- Any additional work will be quoted and approved in writing before proceeding (change order).

JRG Welding Corp — Authorized Signature / Date

Client Acceptance — Signature / Date