



WORK PROPOSAL

Proposal No.: JRG-2026-007

Date: August 27, 2026

Valid for: 30 days

Structural & Ornamental Welding · Aluminum · Steel · Stainless · Exterior Renovation

13796 SW 139 Ct, Miami, FL 33186 · (786) 804-9010 · [Email] · Lic. [License #]

PREPARED FOR

Client: Raul [Last Name]
Project Address: 18398 131st Trail N, Jupiter Farms, FL
Phone / Email: [Client Contact]

PROJECT

Replace the wood railings on both elevated porches with a 42"-high powder-coated aluminum railing system (±200 LF) — permanent, maintenance-free, open modern profile.

1. EXISTING CONDITIONS

The wood railings on both elevated porches are weathered and loose, with split cap boards and a heavy, closed picket look. Approximately **200 linear feet** of railing total (both decks, approx. 26' × 50' each), guard height **42"**.

2. PROPOSED SOLUTION — POWDER-COATED ALUMINUM RAILING, 42"

- **Permanent:** aluminum does not rot, splinter, rust or feed termites — no more cap boards to replace, ever.
- **Factory powder-coat finish** (dark bronze or matte black) — zero painting, zero maintenance.
- **Open, modern profile** — replaces the heavy wood pickets with a clean look that opens the view of the property.
- **Code-compliant:** 42" guard height, 4" sphere rule, engineered post spacing, stainless/coated structural anchors to the framing.

3. SCOPE OF WORK

1. **Demolition:** Remove the existing wood railings on both porches completely (posts, pickets and caps); haul away and legally dispose.
2. **Installation:** Furnish and install the selected 42" aluminum railing system — posts anchored to the deck framing with structural hardware, sections level and rigid, corners and terminations finished with manufacturer components.
3. **Closeout:** Shake-test every section, touch-up, cleanup and walkthrough with owner.

4. PRICE — OWNER SELECTS ONE STYLE

Style (per Idea Board presented)	Rate / LF installed	Est. total (±200 LF)	Select
A — Ranch mesh (Wild Hog®) — 4"×4" wire grid, the farmhouse look	\$ 60.00	\$ 12,000.00	☐
B — Slim vertical balusters (Westbury®/Trex®) — classic, clean	\$ 65.00	\$ 13,000.00	☐
C — Horizontal rod rail (Trex® Signature) — the refined modern look	\$ 80.00	\$ 16,000.00	☐

D — Stainless cable (Key-Link) — maximum open view	\$ 95.00	\$ 19,000.00	☐
TOTAL = SELECTED RATE × FIELD-VERIFIED LINEAR FEET			

Optional add: matching aluminum railing on both rebuilt stairs (±20 LF) at the same selected rate. Footage is estimated at ~200 LF and field-verified before ordering; the selected rate per LF is the contract price. **If this conversion proceeds, the wood railing cap and re-alignment items of Proposal JRG-2026-005 are removed** (that proposal becomes stairs-only, \$1,700).

5. TERMS & CONDITIONS

- **Payment:** [50%] deposit to order the railing system; balance due upon completion and owner walkthrough.
- **Schedule:** Material lead time approx. 2–4 weeks after deposit; installation approx. one (1) week on site, weather permitting.
- **Warranty:** One (1) year on workmanship; railing system per manufacturer warranty (typ. 15 years to lifetime on finish).
- **Exclusions:** Deck boards and framing (separate proposals), stair rebuild (Proposal JRG-2026-005), lighting, painting of any wood.

JRG Welding Corp — Authorized Signature / Date

Client Acceptance — Signature / Date