



WORK PROPOSAL

Proposal No.: JRG-2026-005

Structural & Ornamental Welding · Aluminum · Steel · Stainless · Exterior Renovation

Date: **August 26, 2026**

13796 SW 139 Ct, Miami, FL 33186 · (786) 804-9010 · [\[Email\]](#) · Lic. [\[License #\]](#)

Valid for: **30 days**

PREPARED FOR

Client: **Raul** [\[Last Name\]](#)

Project Address: **18398 131st Trail N, Jupiter Farms, FL**

Phone / Email: [\[Client Contact\]](#)

PROJECT

Railing and stair renewal at both elevated porches (front and rear): new full-length 2×6 railing caps, complete railing re-alignment and re-fastening, and full rebuild of both five-step stair flights.

1. EXISTING CONDITIONS

At both elevated porches (front and rear): the 2×6 railing cap boards are split and weathered with open joints and exposed rusted nails; the railing assemblies have worked loose and are out of plumb; and both five-step stair flights have treads and framing at the end of their service life.

2. SCOPE OF WORK

- Railing caps — both porches (~200 LF):** Remove the existing split cap boards and install new full-length select pressure-treated **2×6 top caps** on both elevated deck railings, fastened with exterior-grade structural screws (no nails), joints cut at 45° over posts and sealed — no open joints, no exposed fasteners.
- Railing re-alignment & re-fastening:** The railing assemblies are loose and out of plumb. **Plumb, straighten and re-secure the complete railing runs on both porches** — posts re-aligned, sections drawn tight, and every connection re-fastened with structural screws so the railings are rigid, with no movement.
- Stair flights — demolish & rebuild (both):** Demolish the existing five-step stair flight at the front porch and at the rear porch. Furnish and install new pressure-treated ground-contact stringers, new treads and galvanized stringer connectors; **stairs and adjoining railing temporarily supported, jacked and shimmed as required** during the work; new caps on the stair rails.
- Disposal:** Haul away and legally dispose of all demolished material.
- Closeout:** Walk every tread and every foot of railing, verify plumb and solid, cleanup.

3. PRICE

Item	Amount
Railing caps — both porches (~200 LF new PT 2×6, screwed, sealed 45° joints)	\$ 1,800.00
Railing re-alignment & re-fastening — both porches, complete runs plumbed and secured	\$ 700.00
Both stair flights — complete rebuild (new stringers, treads, connectors, stair rail caps, temporary support/shimming, demolition & disposal)	\$ 1,700.00

TOTAL — MATERIALS & LABOR	\$ 4,200.00
---------------------------	-------------

Cap footage estimated at ~200 LF, field-verified. This work is independent of the aluminum railing conversion under consideration — if the owner proceeds with aluminum railings, the cap and re-alignment line items are credited accordingly.

4. TERMS & CONDITIONS

- **Payment:** Due upon completion.
- **Schedule:** Approx. 3 working days, scheduled together with other work at the property.
- **Warranty:** One (1) year on workmanship.
- **Exclusions:** Deck boards, balusters and posts beyond re-fastening (replaced only under written change order if found unserviceable), painting/sealing, and repair of concealed rot found at demolition (written change order).

JRG Welding Corp — Authorized Signature / Date

Client Acceptance — Signature / Date